
ST HELENS CANAL RESTORATION FEASIBILITY STUDY




THIS DOCUMENT CONTAINS:

VOLUME 1 Technical Report

VOLUME 5 Technical Appendix
Restoration Proposals Drawings







ST HELENS CANAL FEASIBILITY STUDY VOLUME 1 TECHNICAL REPORT

Prepared by:	All Hewitt.
	J M Hewitt IEng FCIWEM
	Milleuth
	M R P Moss BSc(Hons) DipTP MRTPI
Checked by:	Alloge
Reviewed by:	J N Cooper BEng(Hons) MSc CEng MICE MCIWEM
iteriewed by.	JE Saunders CEng FICE
Authorised by:	J D Carr BSc(Hons) CEng MICE MCIWEM
	J D CALL DOC(110115) CETIG IVICE IVICITY ENT

WS Atkins Consultants Limited WS Atkins House Birchwood Boulevard Birchwood Warrington Cheshire WA3 7WA

Tel: 01925 828987 Fax: 01925 828153 Reference: AY2311.850/JMH/jp/120.7521

Issue No: 05/Date: August 1996

			Page
1.0	INT	RODUCTION	1
	1.1	Form of Report	1
	1.2	Study Objectives	3
	1.3	Approach to the Study	3
	1.4	Consultations	4
2.0	BAC	EKGROUND	5
	2.1	Canal History	5
	2.2	Engineering and Heritage	6
	2.3	Present Condition	8
	2.4	Key Issues Affecting Restoration	14
3.0	HYD	PROLOGY	16
	3.1	History of Canal Water Supplies	16
	3.2	Existing Situation	19
		Pilkington's Canal Feeder	
		Rainford Brook	
		Carr Mill Dam/Black Brook	
		Callands Brook	
		Fiddlers Ferry Power Station	
		Stormwater Systems and Land Drainage	
	3.3	Canal Water Resource Requirements	22
		Lockage Losses	
		Leakage	
		Seepage	
		Evapotranspiration	
		Total Canal Water Demand	

			rage
	3.4	Available Supply	26
		Methodology	
		Surface Water Sources	
		Water Quality	
		Use of Groundwater Supplies	
		Summary of Canal Water Balance	
		Recommended Supply Options for Full Canal Restoration	
	3.5	Interim Supply Arrangement	41
		Existing Situation	
	3.6	Flood Defence Implications	43
		Rainford Brook	
		Havannah Flashes	
		Gemini Business Park	
		Bewsey Lock	
		Sankey Bridges	
		Conclusions	
4.0	CON	STRAINTS ON RESTORATION	47
	4.1	Changed Alignment	47
		Park Road to Old Double Lock	
		Hulme Lock to Bewsey Lock	
	4.2	Contaminated Silt and Fill	51
	4.3	Major Structural Obstacles	54
		M62 Motorway Crossing	
		Sankey Way Culvert	
		Liverpool Road Bridge	
	4.4	Blackbrook Branch	57
5.0	REST	TORATION PROPOSALS	59
	5.1	Approach and Criteria	59
	5.2	Deviation from Original Alignment	60
	5.3	Dimensional Standards	61
	5.4	Construction Details	63

			rag
	5.5	Environmental Enhancement of Canal Track	6'
	5.6	Proposed Restoration Works	6.
	5.7	Section A - Safeway to Corporation Street	69
	5.8	Section B - Corporation Street to Islands Brow	7:
	5.9	Section C - Islands Brow to Blackbrook	73
	5.10	Section D - Old Double Lock to Engine Lock	75
	5.11	Section E - Engine Lock to Penkford Bridge	70
	5.12	Section F - Penkford Bridge to Bradley Lock	70
	5.13	Section G - Bradley Lock to Newton Brook	77
	5.14	Section H - Newton Brook to Winwick and	
		Section J (Part) - Winwick to Dallam (New Hulme Lock)	78
	5.15	Section J (Part) - Dallam (New Hulme Lock) to Bewsey Lock	80
	5.16	Sections K to N - Bewsey to Spike Island	81
	5.17	Section K - Bewsey to Liverpool Road	82
	5.18	Section L - Liverpool Road to Fiddlers Ferry	83
	5.19	Section M - Fiddlers Ferry to Carterhouse Swing Bridge	84
	5.20	Section N - Carterhouse Swing Bridge to Spike Island	85
6.0	REST	CORATION COSTS	86
	6.1	Estimated Costs	86
	6.2	Commentary on Costs	89
7.0	POTE	ENTIAL BENEFITS FROM RESTORATION	94
	7.1	Introduction	94
	7.2	Construction Phase	95
		Local Spending	
		Direct Employment	
		Indirect Employment	

			Page
	7.3	Formal Uses of the Canal	98
		Weekly Boat Hire	
		Short Break Boat Hire	
		Day Boat Hire	
		Trip Boat/Restaurant Boat/Waterbus	
		Private Boats	
	100	Angling	
		Canoeing	
	7.4	Informal Use of the Canal	107
		Walking, Cycling and Horse Riding	
		Gongoozlers	
		Other Informal Uses	
	7.5	Canal Related Development	108
	7.6	Canal Operation and Maintenance	109
	7.7	Post Restoration Impacts on Local Economy	109
		Spending	
		Employment	
	7.8	Conclusions	112
		Summary of Restoration Benefits	
		Cost-Benefit Analysis	
8.0	POTE	ENTIAL SOURCES OF FUNDING	117
	8.1	Introduction	117
	8.2	European Union Funds	117
		European Structural Funds	
		European Community Initiatives	
	8.3	Central Government Funds	119
		Single Regeneration Budget	
	8.4	Lottery Funds	119
		The Millennium Commission	
		National Heritage Memorial Fund	
		Sports Council	

			Page
	8.5	Government Agencies	123
		Countryside Commission	
		English Heritage	
		English Partnerships	
	8.6	Local Authorities	125
	8.7	Private Sector	125
	8.8	• Conclusions	126
9.0	RES'	TORATION STRATEGY	127
	9.1	Restoration in Sections	127
	9.2	Central Section	128
	9.3	Mersey Section	129
	9.4	Warrington Section	129
	9.5	St Helens Section	130
	9.6	Major Obstacles	130
	9.7	Conclusions	131
10.0	POST	T RESTORATION EXPENDITURE AND REVENUE	134
	10.1	Canal Authority	134
	10.2	Expenditure	134
		Water Supply	
		Maintenance	
		Operation	
		Annual Expenditure	
	10.3	Revenue	137
		Boat Licences	
		Mooring Fees	
		Angling Licences	
		Income from Property	
		Revenue from Existing Marinas	
		Annual Income	
	10.4	Balance of Expenditure and Revenue	139

	VOLUME 1. TECHNICAL REPORT	
		Page
11.0	CONCLUSIONS	144
12.0	RECOMMENDATIONS	144
Appe	ndix 1 List of Consultees	


Followed by:-

Volume 5 Technical Appendix - Restoration Proposals Drawings

80.198

LIST OF FIGURES

Figure 1.1	Location Plan
Figure 2.1	Key Plan - Canal Sections
Figure 2.2	Schematic of Canal's Current Status
Figure 3.1	Location of Water Resources in Upper Section of Canal
Figure 3.2	Existing Supply Regime in St Helens
Figure 3.3a	Supply Required Along Canal
Figure 3.3b	Components of Pound Demand
Figure 3.4	Proposed Supply Regime in St Helens
Figure 3.5	Revised Hydraulic Regime
Figure 0 1	Restoration Strategy





ST HELENS MBC



WARRINGTON BC

ST HELENS CANAL

Location Plan



HALTON BC

